

# ALARA Approach - Dismantling Pit 7

Building 147 - Decladding

F. PETITOT / C. DURAIN

11/03/2019




# ***Location of the operations***




# Marcoule Center



## Decladding workshops




# Building 147 decladding workshops




# Pit 7

- Pit 7 was designed to hold liquids during the operational period, and to enable the decanting and storage of graphite from EDF spent fuels and zeolites from cooling pool treatment.
- Height: 7.38 m
- Length: 6.55 m
- Width: 4.55 m
- Usable volume: 176 m<sup>3</sup>
- Covered by a 1m thick concrete ceiling slab



***Worksite***

***phases***



# Emptying and dismantling Pit 7 in the Decladding building

- Retrieval of the waste (sludge + graphite) present in the bottom of the pit
- Internal equipment rinsed
- A0 opening in the ceiling slab enlarged
- Dismantling and removal of the internal equipment
- Pumping system dismantled
- Final pit treatment (removal of polyester + concrete pit bottom and walls, and cleanup of black steel casing).

# Equipment present

Diffuser pot and  
spreading blades  
4 Gy/h


Opening A0

Pit center  
at mid-height  
120 mGy/h

Effluent retrieval pot



Support frame

Wave control plates  
240 to 400 mGy/h






# Worksite setup



# Retrieval of waste from the bottom of the pit

- Use of a pumping SKID:




- The PYTHON arm enabled the suction nozzle to be positioned.


# Rinsing the internal equipment



RETRIEVAL POT



DIFFUSER POT AND ITS SPREADING BLADES




WAVE CONTROL PLATES




# Dismantling the internal equipment and the pumping system

- **Dismantled items cut up using:**
  - a **Brokk 180** equipped with a grinder
  - A **PYTHON** arm equipped with a plasma torch
- **Dismantling the pumping system:**
  - **Rinsing, then winnowing skid and pumping skid dismantled.**
  - **Removal of submerged pump and sludge retrieval pump.**




Skid de vannage se trouvant à l'Ouest du sas d'intervention





# Removal of cut pieces (1/2)

- The highly irradiating pieces were grouped in radiation-protected containers.
- These were lifted up through the pit ceiling and placed in a transfer cask, for containment in a special packaging or a suitable disposal site.



# Removal of cut pieces (2/2)

- The other pieces were grouped in waste containers.
- An irradiation check was carried out by the PYTHON arm equipped with a measurement detector before their removal from the pit .





# Final treatment of the pit

- Removal of the polyester lining and of the concrete tank walls until the black steel tank layer was reached (floor and walls).
- Surfaces chipped off by the Brokk inside the pit.
- Waste removed in suitable packaging.
- Complete radiological testing of the pit state.
- Brokk removed.
- Final cleanup carried out manually by operators.



# *The ALARA Approach*





# Operations carried out by STMI

- STMI carries out operations for AREVA (now ORANO), which is the prime contractor for the CEA (2010)
- STMI set out the ALARA approach associated with the operations (106 pages).
- Validated by the Order Giver after SPR validation.
- Operations planned to last 534 working days, i.e. 2 years
- Forecast collective dose: 114.4 man mSv
- Annual individual dose of 6.5 mSv

 STMI BU Assainissement	Note technique VIDANGE DE LA FOSSE 7 DU DEGANGAGE	RM : CDR/ALC/INT 107 DESTINATAIRE AREVA INC. Page: 9/106
	Date: Rédigé par: Vérifié par:	

DEMARCHE ALARA : VIDANGE ET DEMANTELEMENT DE LA FOSSE 7 DU DEGANGAGE	Révision : 7 Date d'application :
--	--------------------------------------

BON POUR EXECUTION  
 le 23/10/10  
 Date : 23/10/10  
 Nom : TESTA  
 Visa :

NATURE DE LA DEMIERE EVOLUTION			
• Prise en compte des remarques clients émise par mail le 07/10/2010			
DATE	23/10/10	24/10/10	25/10/10
VISA			
NOM	M. CHARAVEL	D. BAUBET	Y. CHEVALIER
FONCTION	Chargé d'œuvre	PCR	Chargé d'œuvre
	Rédacteur	Vérificateur	Approbateur

# Criteria taken into account in the ALARA approach



INTERMEDIARY SLUDGE RETRIEVAL		Option			
Criterion	1	2	3	4	
Delivery time	5.8	5.5	5.0	4.8	
Financial cost	5.5	5.0	6.0	5.5	
Collective equivalent dose	4.0	6.0	4.0	6.0	
Individual equivalent dose	4.0	6.0	4.0	6.0	
Waste volume	6	6	6	6	
Effluent volume	6	6	6	6	
Technical difficulty	3.5	4.0	5.0	3.0	
Security	6	3	6	3	
Safety	6	3	6	3	
TOTAL	46.8	44.5	48.0	43.3	
AVERAGE	5.2	4.9	5.3	4.8	
RANKING	2	3	1	4	

*Model*


*Criterion max value: 6*

*All criteria weighted at 1*

# Main variants studied (1/2)



# Main variants studied (2/2)



# Dose forecasts in 2010

Phase	Before optimization (man mSv)	After optimization (man mSv)	Dose gain (man mSv)
<i>Retrieval of waste in the pit</i>	64.8	45.2	19.6
<i>Rinsing internal equipment</i>	182.6	9.4	173.2
<i>Dismantling internal equipment</i>	80.0	33.0	47.0
<i>Structure treatment</i>	26.9	26.9	0
<b>Totals</b>	<b>354.3</b>	<b>114.4</b>	<b>239.8</b>

# Evolution of the ALARA approach

- Since 2010, the ALARA approach has had 5 revisions (rev.7 → rev.12)
- 5 revisions of the forecast for the waste retrieval
- Discovery of highly irradiating waste (3 Gy/h) whose treatment has meant an increase in the forecast dose of 45 man mSv
- Premature wear on the aspiration pump leading to the need to change it 6 times, and meaning an increase in the forecast dose of 12.5 man mSv

# Operational doses at the end of 2018

Phase	Forecast (man mSv) (Rev.7) 2010	Forecast (man mSv) (Rev.12) 2017	Actual (man mSv)	Dose gain (man mSv)
<i>Retrieval of waste in the pit</i>	45,2	102.7	88.4 <i>Finished</i>	14.3
<i>Rinsing internal equipment</i>	9.4	9.4	2.4 <i>Finished</i>	7.0
<i>Dismantling internal equipment</i>	33.0	33.0	11.1 <i>Running</i>	
<i>Structure treatment</i>	26.8	26.8	<i>Left to do</i>	
<b>Totaux</b>	<b>114.4</b>	<b>171.9</b>	<b>101.9</b>	<b>21.3</b>

# Conclusion

- **For this worksite:**
  - 7 revisions of the ALARA approach before the worksite began
  - 5 revisions since operations began (worksite started in 2010 and not yet finished)
- **On cleanup / dismantling worksites, the ALARA approach is applied continuously and dynamically.**
- **There is a systematic updating of the ALARA approach at each significant change in the worksite, to establish the new dose forecast.**
- **The objective is to guarantee the optimization of individual worker exposure.**





**orano**

Donnons toute sa valeur au nucléaire

FROM RESEARCH TO INDUSTRY

cea

